New 5V5 pitch

Proposed pathway to new 5V5 pitch

Pitched Adjusted West, new drainage provided

Proposed 4.5m High Ball Stop Fencing to Pitch

Changing Block

Canopy

Canopy

Canopy

Proposed Teaching Block

Vehicle Access Gate and Accessible Entrance

Ball Retrieval Gate Access

Proposed 2.4m High Mesh Fencing to Grass Pitches

Existing 106m x 70m (incl. runoff) Grass Pitches & 400m Running Track

Proposed New and relocated Cycle Storage

Proposed Landscaping/ Hardstanding

Entrance

Proposed Floodlit 106m x 70m (incl. runoff) 3G Pitch

School Access via Pedestrian Gate

Existing School Building

Please see drawings and documentation provided by SSL for details incl. fencing

Entrance

Proposed Dining Hall Infill Extensions

Vehicle Access Gate

Proposed Cycle Storage

Teece Drive



Proposed 5V5 Mini Soccer Pitch - **1:1000**

Marked out and drained - suitable for Under 7's and Under 8's Mini Soccer.

For more information on 5V5 pitch please see Bond Bryan drawing HTAT-BBA-ZZ-XX-DR-A-1007 'Proposed 5V5 Mini Soccer Pitch Location' and Natural Turf Solutions drawings and documentation.

This document is © Bond Bryan Architects Ltd.
If in doubt ASK. Drawing measurements shall not be obtained by scaling. Verify all dimensions prior to construction.
Immediately report any discrepancies on this document to the Originator. This document shall be read in conjunction with associated models, specifications and related consultants' documents.

Native model: 21092-Site

North

N

Existing site plan base drawing provided by Telford and Wrekin Council

Key

- Existing Building
- Proposed Building
- Proposed Vehicular Asphalt
- Proposed Asphalt Footway
- Proposed 3G AGP Pitch surface
- Proposed Topsoil and Turf
- Proposed 3m High Mesh Fencing to Grass Pitches
- Proposed 1.8m High Close-boarded Timber Acoustic Fencing
- Proposed 4.5m Ball Stop Fencing

rev	description	drawn	checked	date
P10	Fence reduced to 2.4m / Fire tender access increased	NH	AM	13/10/2021
P09	Additional gate added to fencing to West pitches for ball retrieval. 5V5 pitch added	NH	AM	07/10/2021
P08	Ball stop fence adjacent to North, central pitch adjusted away from runoff	NH	AM	29/09/2021
P07	Permeable paving removed	NH	AM	14/09/2021
P06	Stage 3 Issue	NH	SG	03/09/2021
P05	Planning Issue	NH	BR	20/08/2021
P04	Pitch adjacent to TB adjusted West, Fence to West Pitches moved out by 1m.	NH	BR	13/08/2021
P03	Landscape updated, cycle stores added, acoustic fencing added	NH	BR	11/08/2021
P02	3G Pitch added	NH	AM	06/08/2021
P01	First issue	NH	AM	04/08/2021

B O N D B R Y A N

i2 Business Centre 2 Snow Hill Birmingham
West Midlands B4 6GA UK

t 0207 812 0601
e info@bondbryan.co.uk
w www.bondbryan.co.uk

Willmott Dixon

Holy Trinity School

Holy Trinity Academy School

Proposed Site Plan

Originator project ref	Purpose of Issue
21092	**Design**
Scale(s)	Status
1:500, 1:1000	**S1 Suitable for Planning**
Paper size	Revision
A1	**P10 Preliminary**

project	originator	volume	level	type	role	number	status	revision
HTAT	BBA	ZZ	XX	DR	A	1005	S1	P10